

ACHIZITIOARE:

OBIECTIV: 4046 Reabilitare cladire statie de pompare si imprejmuire zona de protectie sanitara cu regim sever la gospodaria de apa din Baile 1 Mai.

OBIECT: 400 005 GARD DE PROTECTIE SI CURTE INT

LISTA CUPRINZAND CANTITATILE DE LUCRARI

DEVIZUL OFERTA: 0108

CATEGORIA DE LUCRARI: POARTA

Nr.crt.	Capitolul de lucrari	UM	Cantitate	Pret unitar	Valoare:
				a) Material b) Manopera c) Utilaj d) Transport Total (a+b+c+d) (lei/UM)	Material (3x4a) Manopera (3x4b) Utilaj (3x4c) Transport (3x4d) Total (5+6+7+8) (lei)
Sectiune tehnica				Sectiune financiara	
0	1	2	3	4	5-9

CAP. 1.

SUBC. 1.

100.000 %

1. TSA02C1 SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ VERT.NESPR.IN PAM.NECOEZ.SI SL.COEZ.ADINC.<0,75M T.TARE

MC 0.864

2. TSD01C1 IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,STRAT UNIFORM 10-30CM.GROS CU SFARIM.BULG.TEREN TARE

MC 1.020

3. CA01A1 TURNARE BETON SIMPLU IN FUNDATII(CONTINUE,IZOLATE)SI SOCLURI CU VOLUM <3MC

LA1:10173/subset:0/31/0500311.BETON: C12/15 - BC 15 - B 200 , T3/T4, 0-16>1.008 MC

MC 0.864

4. CL21A1 MONTAREA CONFECTIILOR METALICE DIVERSE INGLOBATE IN BETON

LA1:10107/subset:0/1/6309886.CONFECTII METALICE INGLOBATE IN BETON>1 KG

KG 165.000

0	1	2	3	4	5-9	
5.	TRA06A10	TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTOBETONIERA DE 5,5MC DIST. =10KM	\$	TO	2.080	
6.	CK16A1	PORTI METALICE CU RAME DIN OTEL PROFILAT SI CU IMPLETITURA DE SIRMA ZINCATA INCLUSIV ACCESORIILE		MP	10.000	
7.	CK25C1	LUCRARI ACCESORII LA TIMPLARIE BROASCA APLICATA SISTEM YALE		BUC	1.000	
8.	CL20C1	MONTAREA CONFECTIILOR METALICE APARENTE: DIVERSE EXCLUSIV PARAPETI, BALUSTRAZI, CHEPENGURI		KG	135.000	
9.	1153555	PLASA SIRMA SUDATA ZINCAT+PLASTICAT H=2000MM		M	6.000	
10.	TRA02A10	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELOR CU AUTOCAMIONUL PE DIST.= 10 KM.	\$	TO	1.500	

Cheltuieli directe:	Materiale: 5	Manopera: 6	Utilaje: 7	Transport: 8	Total: 9
----------------------------	------------------------	-----------------------	----------------------	------------------------	--------------------

din care:

utilaje electrice:

utilaje termice:

C.A.S.	20.800 %
Somaj	0.750 %
Sanatate	6.050 %
Accidente	0.279 %
Alte cote 1	0.000 %
Alte cote 2	0.000 %
Alte cote 3	0.000 %

TOTAL CHELTUIELI DIRECTE

Cheltuieli indirecte:

Profit:

TOTAL GENERAL

OFERTANT:

